Planting procurement spec — Landscape Works

Greenfield Residences · supply, measurement and pricing rules for the bill of quantities · 2026 (sample)

1. Plant material

- Nursery grown, root-balled, true to the botanical name on the plant schedule.
- Trees: caliper measured 1.0 m above ground; height and spread within 10% of the schedule.
- Substitutions only with the designer's written approval.

2. Measurement

- Quantities are measured net from the drawings; plant quantities on plan take precedence over the schedule.
- Trees and shrubs by number of plants; hedges by number of plants at the stated spacing, not by length.
- Beds, lawn and paving by area in m²; edges by length in m.

3. Pricing

- Unit rates include supply, planting and 12 months of establishment maintenance.
- Prices in NT$, excluding the 5% business tax; overhead and profit stated separately.

4. Paving

Code	Material	Specification
PV-1	Permeable pavers	concrete, 200 x 100 x 80 mm, on 30 mm sand
PV-2	Exposed aggregate	100 mm, 6-10 mm aggregate
PV-3	Grass pavers	concrete grid 400 x 400 x 80 mm, soil and sod

Material samples and photos are submitted for approval before ordering.